

DEMOLITION NOTES

1. THE CONTRACTOR IS TO ACCEPT FULL RESPONSIBILITY FOR THE STABILITY AND STRUCTURAL INTEGRITY OF THE EXISTING STRUCTURES WITHIN AND ADJACENT TO THE WORKS.

2. THE CONTRACTOR SHALL SUBMIT, AND HAVE AGREED WITH THE ENGINEER, HIS PROPOSALS FOR TEMPORARY SUPPORTS AND METHOD OF WORKING. THESE ARE TO INCLUDE ALL NECESSARY CALCULATIONS IF REQUIRED.

3. THE CONTRACTOR IS TO CARRY OUT ALL AGREED PROPPING TO WALLS AND FLOORS PRIOR TO THE REMOVAL OF ANY WALLS.

4. ALL NEW OPENINGS ARE TO BE FORMED BY CAREFULLY SAW-CUTTING. ALL DEFECTIVE MASONRY OR CONCRETE WORK IS TO BE REPAIRED OR RE-BUILT AS NECESSARY WITH ALL NEW MASONRY BEING BONDED IN AT JUNCTIONS WITH OTHER WALLS.

5. NO VARIATION IN THE STRUCTURAL DETAILS SHOWN ON THESE DRAWINGS WILL BE PERMITTED WITHOUT THE WRITTEN APPROVAL OF THE ENGINEER.